



नरैनापुर गाउँपालिका गाउँ कार्यपालिकाको कार्यालय

नरैनापुर, बाँके
लुम्बिनी प्रदेश, नेपाल



दररेट पेश गर्ने सम्बन्धी सूचना
पहिलो पटक प्रकाशित मिति: २०८२/०२/०८

श्री सम्बन्धित सम्पूर्ण सप्लायर्स/निर्माण फर्महरु

प्रस्तुत विषयमा नरैनापुर गाउँपालिकाको आ.व. २०८१/८२ को विनियोजित बजेट तथा कार्यक्रमको अधिनमा रही तपसिल आयोजनाको निर्माण कार्यका लागि इच्छुक निर्माण फर्म/कम्पनीले आवश्यक कागजात सहित सूचना साथ संलग्न BOQ भरी सूचना प्रकाशित मितिले ७ दिन भित्र सिलबन्दी दररेट यस कार्यालयमा पेश गर्नुहुन अनुरोध छ ।

तपसिल

सी. नं.	योजनाको नाम/ठेगाना	कुल रकम (भ्याट सहित)	दर्ता गर्ने समय/मिति र ठेगाना	कैफियत
१	मटेहिया स्वास्थ्य चौकीको मर्मत सम्भार, नरैनापुर-५, बाँके	२,४०,६६६/२४ (अक्षरेपी दुई लाख चालिस हजार छ सय छैसठ्ठी रुपैयाँ चौबिस पैसा मात्र)	मिति २०८२/०२/१४ गते बेलुकी ५:०० बजे (कार्यालय समक्ष भित्र) (योजना शाखा)	प्रमाणित BOQ यस कार्यालयको वेबसाइट वा योजना शाखाबाट प्राप्त गर्न सकिनेछ । खोल्ने मिति २०८२/०२/१६ गते शुक्रवार बिहान ११:०० बजे (कार्यालय समय भित्र) (योजना शाखा)

संलग्न गर्नुपर्ने कागजात

१) व्यवसाय दर्ता प्रमाणपत्र, इजाजत पत्र, कर चुक्ता प्रमाण पत्र (२०८०/०८१), नविकरण ।

२) प्रमाणित BOQ को मा दररेट भरी निर्माण फर्म/कम्पनीले सहि छाप सहित पेश गर्नु पर्ने ।

नोट - : सम्पूर्ण माग गरेको कागजात सहितको सिलबन्दी खाम यस कार्यालयको योजना शाखामा कार्यालय तोकिएको समय भित्र दर्ता गरिसक्नु पर्ने छ । (सम्पर्क नं. ९८५८०५६७१०)

(नवराज खली)

प्रमुख प्रशासकीय अधिकृत



NARAINAPUR RURAL MUNICIPALITY
OFFICE OF RURAL MUNICIPAL EXECUTIVE
LUMBINI PROVINCE, NEPAL

Bill of Quantities.

योजनाको नाम:- मटहलिया स्वास्थ्य चौकीको भर्नात सम्भार नरैनापुर गा.पा-५, बाँके
कार्यक्रमावधि/निकाशको नाम र कार्य/नियमन हुने स्थल: नरैनापुर गा.पा-५, बाँके

Date		Description of Items		Quantity	Unit	Figures	Contractor's Rate in NRs. words.	Amounts in NRs.	Remarks.
A		General work							
		Project Information Board		1.00	No				
B		Civil Work							
1		Brick Work							
		First class chimney Bhatta Brick masonry work in cement sand (screened) mortar 1:4 in super structure in line & level including cleaning, wetting the brick, with proper mixing the mortar, laying & packing the joint and curing the job all complete as per dra		3.22	Cum				
2		PCC for RCC Work							
		P.C.C. (Plain cement concrete) M20 work in foundation & floor with cement sand & aggregate 10 to 38 mm gauge, Proper mixing with mixture machine laying & compaction in proper line & level, curing the job as per specification & instruction of site engine		5.06	Cum				
3		Formwork							
		Centering, shuttering with approved material (19mm ply) for all kind of RCC work (column) including all necessary nailing, propping, scaffolding, saging, supporting, bracing etc in proper line and level all complete as per drawing, specification and instruction		3.87	sqm				
4		Steel Reinforcement							
		TMT Steel Reinforcing bar(Fe500) of all sizes for RCC including supply, straightening, cutting, laying, bending & binding with binding wire and fixing in position all complete as per design, drawing, specifications and instructions of site Engineer/Consult		492.70	kg				
5		Plaster & finishing work							
		12.5mm thick cement sand plaster 1:4 inside wall, outside wall & ceiling etc. of good finish including ranking the joint, wetting the surface and curing the work all complete as per drawing, specification and instruction of site Engineer/Consultant.		46.40	Sqm				
		Sub Total							
		Total Amount NRs.							
		Total Amount in Words							
		13% VAT :							
		Grand Total :							
		Contractor's firm :							
		Seal :							
		Proprietor's Name :							
		Address :							



योजनाको नाम:- मटाहिया स्वास्थ्य चौकीको मर्मत सम्भार नरैनापुर गा.पा-५, बाँके
कार्यक्रमा/योजनाको नाम र कार्यान्वयन हुने स्थत: नरैनापुर गा.पा-५, बाँके

Bill of Quantities.

Date		Description of Items	Quantity	Unit	Figures	Contractor's Rate in NRs. words.	Amounts in NRs.		Remarks.
SN									
Telephone :		Mobile:							
Signature :		E-mail :							
Date :									

